

TEST REPORT OF OCR TESTER

Report No.	QS472-14070405	Date of Manufacture	Jul-14
Date of test	2014. 7.4	Date of issue	2014. 7.4
Item Code	72313460375		
Description	TOTAL ASS'Y,SUSOL ACB OCR TESTER		
Applied Standard	The Company Standard		
Rated Voltage	DC 24V		
Tested by	Seon-Yong, Jung <i>26 H 13</i>		

Test results

No.	Items of test	Test standard	Test Results
1	Visual and construction inspection	Shall be no defects - Omission of part - Erased marking - Damaged and burned part	Good
2	Soldering test	Shall be no defects - Miss soldering - Circuit Short - Pin hole	Good
3	Operation test	Short Time Delay : 11In(tsd 0.4) → 0.34~0.46sec	Good
		Instantaneous : 16.5In → ≤ 0.04sec	
		Ground Fault : 1In(tg0.4) → 0.32~0.48sec	Good
Judgement		Pass	